vesmaco.com synthetic resins for sport and civil surfaces

Vesmaco di Cacciani Claudia
Via Cassolo 15, 60030 Monsano (AN) Italy - Tel. +39 0731 60070
P.iva 02622300420 - vesmaco@vesmaco.com - www.vesmaco.com

To the kind attention of Mr. Jannes Wolff.

SKEELERCLUB OOST VELUWE
Kommerseweg 2a 8181LZ
Heerde
Email: info@skeelerhuus.nl

Monsano, 13/10/2020

Subject: ***OFFER FOR THE CONSTRUCTION OF A ROLLER-SKATING TRACK IN durflex® 101 sp roller professional - HOMOLOGATED BY*** WORLD SKATE OVER THE APPROPRIATE ASPHALT SUPPORT ALREADY DISPOSED BY YOU.
Project: ***Heerde – The Netherlands***

Further to your kind request, for which we thank you, it is a pleasure for us to submit to you our offer for the system mentioned above and described herewith under:

durflex® 101 sp roller professional – WORLD SKATE HOMOLOGATED SYSTEM
Construction (supply and laying) of an outdoor-indoor flooring, specific for the practice of roller-skating at high competitive level, either for national and international events. It is obtained by creating a thick coating, through the pouring of the special system/cycle ***durflex® 101 sp roller professional,*** *homologated by* ***WORLD SKATE*** *onto a special support made of bituminous conglomerate (asphalt). This coating is also suitable for extreme climates with excellent resistance to ice. Delimitation lines included according to rope rules by WORLD SKATE. Maintenance-free flooring. The use is possible even when wet.*

COLOR: ***upon request***

DESCRIPTION	***QUANTITY***	***UNIT PRICE***	***TOTAL***
Supply and laying of ***durflex 101 sp roller professional***	*3647m2*	*€ 30,00*	***€ 109.410,00***
Supply and application of self-adhesive stripes for the no skating zone	*1100 pieces*		***€ 5.300,00***
Transport of the materials (*)	*1*		***€ 2.150,00***
Travel costs for Vesmaco's technicians (*)	*1*		***€ 1.068,00***
Board and lodging for Vesmaco's technicians (*)	*Approx. 16 days*		***€ 2.700,00***
TOTAL PRICE			***€114.710,00 + ANCILLARY COSTS TO BE CONFIRMED***

(*) all the items in red have to be recalculated once the order will be confirmed.

OFFER
If you want to insert two (2) Vesmaco's logos on the inside of the track, € 1500.00 will be reduced from the total amount to be paid. The materials and the stencil necessaries to "draw" the logo on the floor will be provided by us at no additional cost.

Vesmaco di Cacciani Claudia
Via Cassolo 15, 60030 Monsano (AN) Italy - Tel. +39 0731 60070
P.iva 02622300420 - vesmaco@vesmaco.com - www.vesmaco.com

AT YOUR CHARGE:

- *All the costs listed in the table above at page 1;*
- *Costs for the necessary documents for the development of the work by our technicians like: visas, permits and/or others;*
- *Possibility of having 2/3 people of your Company/Association at our workers disposal for practical works.*

SALES CONDITIONS

EXECUTION OF WORKS:	*To be established;*
PAYMENT:	*100% in advance or, however, secured by letter of credit (the cost for the L/C will be added to the total amount to be paid);*
VALIDITY OF THE OFFER:	*6 months;*
AT THE END OF WORKS:	*After having received the entire payment, issue of certificate (That specify the number and date of the invoices) proofing the effected laying of the homologated flooring* ***durflex® 101 sp roller professional*** *for the roller rink.*

NOTES:

- ***Our technicians viewing and considering suitable (at sight) the treatment of an asphalt surface do not and cannot take on the responsibility of how the mix of the asphalt has been done, least of all the correct realization of the underlying base. Both elements are very important and, if they haven't been done in a correct way, they may cause subsequent and unpredictable problems after the application of the top coating that are not due to the finish treatment;***
- *The application of the water based system durflex® roller will be possible only with good weather conditions (absence of rain, humidity, suitable temperatures) sanctioned only by our technicians;*
- *The application time depends on the aforementioned elements.*
- *The calculation of the points where the delimitation line must be drawn will be done by your specialized topographer. Our technicians will simply trace the line where you indicate. Therefore, the responsibility for any non-compliance will be at your charge.*

We remain at your disposal for any further technical and/or commercial information you may need.
We look forward to hearing from you soon.

VESMACO
Export Department
Sofia Mazzarini